

PERMIT TO ALTER A BODY OF WATER

Pursuant to the *Water Resources Act*, SNL 2002 cW-4.01, specifically Section(s) 48

Date: **APRIL 30, 2024**

File No: **534-05**
Permit No: **ALT13608-2024**


Permit Holder: **Maritime Resources Corp**
2 Industrial Park
Springdale, NL
A0J 1T0
perry@maratimegold.com

Attention: **Mr. Perry Blanchard**

Re: **Maritime Resources - Point Rousse Project - Tailing Excavation**

Permission is hereby given for : **excavation of the tailings in Phase 2 Tailings Dam and construction of divider berms to provide setting capacity to facilitate wash plant operations as detailed in the application from Maritime Resources on March 26, 2024 and additional information provided on April 4, 2024 and April 12, 2024.**

- This Permit does not release the Permit Holder from the obligation to obtain appropriate approvals from other concerned municipal, provincial and federal agencies.
- The Permit Holder must obtain the approval of the Crown Lands Administration Division if the project is being carried out on Crown Land.
- This Permit is subject to the terms and conditions indicated in Appendices A and B (attached).
- It should be noted that prior to any significant changes in the design or installation of the proposed works, or in event of changes in ownership or management of the project, an amendment to this Permit must be obtained from the Department of Environment and Climate Change under Section 49 of the *Water Resources Act*.



(for) MINISTER

APPENDIX A
Terms and Conditions for Permit

Dam/Reservoir Design

1. The dam and appurtenant structures shall be constructed at the following coordinates:

Name	Latitude (decimal degrees)	Longitude (decimal degrees)
Phase 2 Tailings Dam	49.96473	-56.12828

2. The dam(s) must have the following dimensions:

Name	Height of Dam (m)	Spillway Elevation (m)	Maximum Water Elevation (m)	Minimum Water Elevation (m)	Minimum Freeboard (m)
Phase 2 Tailings Dam	25	72.5	73.2	68.0	0.8

3. To safely convey peak flows the dam(s) must be designed according to the following hydraulic criteria:

Name	Design Return Period (years)	Minimum Flow Capacity (m ³ /s)
Phase 2 Tailings Dam	2/3 of 1000 and PMF	25

4. Reservoirs must be provided with a spillway of adequate capacity to safely discharge design flows at non-erosive velocities without causing flooding of the reservoir or damage to the spillway or section downstream channel.
5. The dam and associated works must be designed and constructed under the direct supervision of an engineer eligible for membership with the Professional Engineers and Geoscientists of Newfoundland and Labrador (or equivalent Canadian organization) who is able to demonstrate competence in the design, construction, and surveillance of dams.
6. The dam and associated works shall be designed according to the Canadian Dam Association Dam Safety Guidelines and associated Bulletins (most recent edition).

Dam Construction

7. The dam and spillway must be inspected regularly to identify any indications of structural failure, leaking, erosion or other problem so that immediate action can be taken to rectify the problem.
8. The upstream embankment slope shall remain 2.5 horizontal to 1 vertical.
9. Reservoir shorelines with moderately steep slopes or vulnerability to wave induced erosion, must be adequately protected with armour stone, rip-rap, or by other suitable measures.

10. All exposed tailing surfaces shall be capped with waste rock.
11. Organic soils shall be placed on the tailings surface and embankment crests. Areas shall be vegetated.
12. Fill material must be obtained from an approved quarry site. It must not be taken from beaches or streams, and must not be dredged from a body of water.
13. Visual monitoring and measurement of the construction area shall be conducted during rockfill placement on tailings, including, but not limited to, daily shift reports to document work progress, displacement estimates, and timely identification of potential hazards.
14. Weekly survey of the construction advancement shall be conducted.
15. Each rise of rockfill surface on underlying tailings shall be tested for displacement to confirm stability.
16. Excavation of rockfill adjacent to Phase 1 Tailings Dam downstream toe is prohibited.
17. No excavation or rockfill placement shall be permitted within 15 metres of the Phase 2 Tailings Dam geomembrane liner on the upstream embankment face.
18. The transportation of labour and materials to the site must be along existing access roads.
19. The work must meet the requirements of the Environmental Protection Plan (latest approved version) for the project.
20. Work must be conducted in dry conditions.

Dredging/Debris Removal

21. Alteration of the natural minimum streamflow is not permitted in order to preserve aquatic life.
22. The natural course of any stream must not be altered.
23. Dredging activity must only be carried out during periods when wind, wave and tide conditions minimize the dispersion of silt and sediment from the work site.
24. A water quality monitoring program is not required at this time. However, the Department reserves the right to require that the Permit Holder sample, analyse, and submit results of water quality tests, for the purpose of ensuring that the water quality is maintained within acceptable guidelines. All analyses must be undertaken by a CALA accredited laboratory.

Dam Safety

25. The dam has been conditionally classified in the HIGH Consequence category based on the 2007 Canadian Dam Association (CDA) guidelines. To meet the CDA's Dam Safety guidelines (Current Edition) for dams of this classification, the owner must:
 - Carry out an annual Dam Safety Inspection and provide the results to this Department,
 - Carry out a Dam Safety Review and submit a Dam Safety Report to this Department a maximum of every **seven years**,
 - Develop an Operation, Maintenance and Surveillance (OMS) Manual for the operation and closure phases,
 - Prepare an Emergency Preparedness Plan (EPP).

General Alterations

26. Any work that must be performed below the high water mark must be carried out during a period of low water levels.

27. Any flowing or standing water must be diverted around work sites so that work is carried out in the dry.
28. Water pumped from excavations or work areas, or any runoff or effluent directed out of work sites, must have silt and turbidity removed by settling ponds, filtration, or other suitable treatment before discharging to a body of water. Effluent discharged into receiving waters must comply with the *Environmental Control Water and Sewage Regulations, 2003*.
29. All operations must be carried out in a manner that prevents damage to land, vegetation, and watercourses, and which prevents pollution of bodies of water.
30. The use of heavy equipment in streams or bodies of water is not permitted. The operation of heavy equipment must be confined to dry stable areas.
31. All vehicles and equipment must be clean and in good repair, free of mud and oil, or other harmful substances that could impair water quality.
32. During the construction of concrete components, formwork must be properly constructed to prevent any fresh concrete from entering a body of water. Dumping of concrete or washing of tools and equipment in any body of water is prohibited.
33. Wood preservatives such as penta, CCA or other such chemicals must not be applied to timber near a body of water. All treated wood or timber must be thoroughly dry before being brought to any work site and installed.
34. Any areas adversely affected by this project must be restored to a state that resembles local natural conditions. Further remedial measures to mitigate environmental impacts on water resources can and will be specified, if considered necessary in the opinion of this Department.
35. The bed, banks and floodplains of watercourses, or other vulnerable areas affected by this project, must be adequately protected from erosion by seeding, sodding or placing of rip-rap.
36. All waste materials resulting from this project must be disposed of at a site approved by the Department of Digital Government and Service NL.
37. Periodic maintenance such as painting, resurfacing, clearing of debris, or minor repairs, must be carried out without causing any physical disruption of any watercourse. Care must be taken to prevent spillage of pollutants into the water.
38. The owners of structures are responsible for any environmental damage resulting from dislodgement caused by wind, wave, ice action, or structural failure.
39. Sediment and erosion control measures must be installed before starting work. All control measures must be inspected regularly and any necessary repairs made if damage is discovered.
40. The attached Completion Report (Appendix C) for Permit No. 13608 must be completed and returned to this Department upon completion of the approved works. Pictures must be submitted along with the completion report, showing the project site prior to and after development.
41. This Permit is valid for two years from the date of issue. Work must be completed by that date or the application and approval procedure must be repeated. The following term(s) are valid for the life cycle of the structure: 7, 17, 25.
42. The location of the work is highlighted on the Location Map for this Permit attached as Appendix D.

APPENDIX B

Special Terms and Conditions for Permit

1. The Permit Holder and its agent(s), subcontractor(s), and consultant(s) shall keep all systems and works in good condition and repair and in accordance with all laws, by-laws, directions, rules and regulations of any governmental authority. The Permit Holder or its agent(s), subcontractor(s), or consultant(s) shall immediately notify the Minister if any problem arises which may threaten the structural stability of the systems and works, endanger public safety and/or the environment or adversely affect others and/or any body of water either in or outside the said Project areas. The Permit Holder and its agent(s), subcontractor(s), and consultant(s) shall be responsible for all damages suffered by the Minister and Government resulting from any defect in the systems and works, operational deficiencies/inadequacies, or structural failure.
2. The Permit Holder and its agent(s), subcontractor(s), and consultant(s) shall operate the said Project and its systems and works in a manner which does not cause any water related and/or environmental problems, including but not limited to problems of erosion, deposition, flooding, and deterioration of water quality and groundwater depletion, in or outside the said Project areas. The Permit Holder and its agent(s), subcontractor(s), and consultant(s) shall be responsible for any and all damages associated with these problems caused as a result of changes, deficiencies, and inadequacies in the operational procedures by the Permit Holder or its agent(s), subcontractor(s), or consultant(s).
3. If the Permit Holder or its agent(s), subcontractor(s), or consultant(s) fails to perform, fulfil, or observe any of the terms and conditions, or provisions of this Permit, as determined by this Department, the Minister may, without notice, amend, modify, suspend or cancel this Permit in accordance with the *Water Resources Act*.
4. The Permit Holder and its agent(s), subcontractor(s), and consultant(s) indemnify and hold the Minister and Government harmless against any and all liabilities, losses, claims, demands, damages or expenses including legal expenses of any nature whatsoever whether arising in tort, contract, statute, trust or otherwise resulting directly or indirectly from granting this Permit, systems and works in or outside the said Project areas, or any act or omission of the Permit Holder or its agent(s), subcontractor(s), or consultant(s) in or outside the said Project areas, or arising out of a breach or non-performance of any of the terms and conditions, or provisions of this Permit by the Permit Holder or its agent(s), subcontractor(s), or consultant(s).
5. This Permit is subject to all provisions of the *Water Resources Act* and any regulations in effect either at the date of this Permit or hereafter made pursuant thereto or any other relevant legislation enacted by the Province of Newfoundland and Labrador in the future.
6. This Permit shall be construed and interpreted in accordance with the laws of the Province of Newfoundland and Labrador.

- cc: Alex McIntyre
Knight Piesold Ltd
200 - 1164 Devonshire Ave.
North Bay ON
P1B 6X7
amcintyre@knightpiesold.com
- cc: Ms. Paula Dawe, P.Eng.
Manager, Water Rights, Investigations and Modelling Section
Water Resources Management Division
Department of Environment and Climate Change
P.O. Box 8700
4th Floor, West Block, Confederation Building
St. John's, NL A1B 4J6
pauladawe@gov.nl.ca
- cc: Ms. Deneen Spracklin, P.Eng.
Manager, Drinking Water and Wastewater Section
Water Resources Management Division
Department of Environment and Climate Change
P.O. Box 8700
4th Floor, West Block, Confederation Building
St. John's, NL A1B 4J6
dspracklin@gov.nl.ca

Appendix C - Completion Report

Pursuant to the *Water Resources Act*, SNL 2002 cW-4.01, specifically Section(s) 48

Date: **APRIL 30, 2024**

File No: **534-05**
Permit No: **ALT13608-2024**

Permit Holder: **Maritime Resources Corp**
2 Industrial Park
Springdale, NL
A0J 1T0
perry@maritimegold.com

Attention: **Mr. Perry Blanchard**

Re: **Maritime Resources - Point Rousse Project - Tailing Excavation**

Permission was given for : **excavation of the tailings in Phase 2 Tailings Dam and construction of divider berms to provide setting capacity to facilitate wash plant operations as detailed in the application from Maritime Resources on March 26, 2024 and additional information provided on April 4, 2024 and April 12, 2024.**

I (the Permit Holder named above or agent authorized to represent the Permit Holder) do hereby certify that the project described above was completed in accordance with the plans and specifications submitted to the Department of Environment and Climate Change and that the work was carried out in strict compliance with the terms and conditions of the Permit issued for this project.

Date: _____ Signature: _____

This completion report must be completed and forwarded to the following address upon completion of the approved work.

Department of Environment and Climate Change
Water Resources Management Division
PO Box 8700
St. John's NL A1B 4J6

APPENDIX D
Location Map for Permit

