

PERMIT TO CONSTRUCT

Pursuant to the *Water Resources Act*, SNL 2002 cW-4.01, specifically Section(s) 37, 61, 48

Date: **DECEMBER 10, 2024**

File No: **844.199.001**

Permit No: **WS14023-2024**


Permit Holder: **Town of Wabana
P.O. Box 1229
Wabana, NL
A0A 4H0
jordonblackwood@townofwabana.net**

Attention: **Jordan Blackwood**

Re: **Wabana - West Dam Water Supply Phase 4 (Waterline)**

Permission is hereby given for : **the installation of 270 m of 50 mm PE waterline and all related appurtenances to connect Davidson Well (WS-G-0879) to the Scotia Road Well building (WS-G-0879) as described in the drawings titled, "West Dam Water Supply Phase 4 (Waterline)" as received from Englobe on August 2, 2024; 17-GI-21-00087.**

- This Permit does not release the Permit Holder from the obligation to obtain appropriate approvals from other concerned municipal, provincial and federal agencies.
- The Permit Holder must obtain the approval of the Crown Lands Administration Division if the project is being carried out on Crown Land.
- This Permit is subject to the terms and conditions indicated in Appendices A and B (attached).
- It should be noted that prior to any significant changes in the design or installation of the proposed works, or in event of changes in ownership or management of the project, an amendment to this Permit must be obtained from the Department of Environment and Climate Change under Section 49 of the *Water Resources Act*.



(for) MINISTER

APPENDIX A
Terms and Conditions for Permit

Water & Sewer General

1. The works proposed must satisfy the requirements of the latest applicable codes and standards, and be consistent with or otherwise address the design criteria set out in this Department's publication *Guidelines for the Design, Construction, and Operation of Water and Sewerage Systems, 2005*, and as amended from time to time.
2. The work must be undertaken in strict compliance with the submitted documents and the latest version of the *Municipal Water, Sewer and Roads Master Construction Specifications*. A copy of all documents, including the *Municipal Water, Sewer and Roads Master Construction Specifications* must be available for viewing at the construction site office at all times.
3. Liaison is to be maintained with the Environmental Scientist representing the Drinking Water and Wastewater Section of this Department, during the construction and operation of the project. They shall be notified of the pre-construction and post-construction meetings so that they may attend, if deemed necessary. They can be reached at telephone (709) 729-2558.
4. Officials of this Department may visit the project from time to time to ensure that work is carried out within the provisions of this Permit, and is not creating any environmental hazard.
5. Any changes in the approved works, or works other than those specified in the application, must be submitted, in writing, to this Department, and approved, in the form of an Amendment to this Permit, prior to any work.
6. Copies of this Permit, as well as any subsequent Amendments, must be provided to the contractor(s) who will be carrying out these works, and to the engineer's site representative.
7. The drinking water and wastewater system shall be operated and maintained in accordance with the Permit to Operate issued by this Department.
8. Management of stormwater is the responsibility of the municipality or LSD. Stormwater management should focus on ensuring that the post-development stormwater runoff rate will be equal to or less than the pre-development runoff rate. Any stormwater runoff has the potential to contribute to flooding downstream which may have liability issues for the municipality or LSD if not managed properly.
9. The Owner must update any drawings maintained of the drinking water or wastewater system to reflect the modification or replacement of the works, where applicable.

Water Systems

10. All new waterlines and appurtenances shall be hydrostatically tested in accordance with the *Municipal Water, Sewer and Roads Specifications*.
11. All components, lubricants and chemicals provided shall be compatible for use with drinking water and shall meet the requirements of ANSI/NSF 60 Drinking Water Treatment Chemical Standard and ANSI/NSF 61 Drinking Water and System Component Standard and any other standard applicable to potable water.
12. Drains in valve chambers shall be equipped with a backwater valve and screening to prevent the entry of insects, birds, and rodents.
13. All new lines and appurtenances must be disinfected by an approved method described in the latest edition of the AWWA C651 Standard for Disinfecting Watermains and using only chlorine products that meet the NSF 60 standard.

14. After final flushing and before the new water main is commissioned into service, bacteriological sampling must be conducted as per the latest edition of the AWWA C651 Standard for Disinfecting Watermains. Two acceptable options are available: (1) two consecutive sets of bacteriological samples, taken at least 16 hours apart, must be collected and tested for bacteriological quality, or (2) following a 16 hour rest period two consecutive sets of samples, taken 15 minutes apart, must be collected and tested for bacteriological quality. Sets of samples shall be collected for every 366 m of new water main including the end of the main line and the end of each branch line. These sampling locations shall be determined by the engineer. **A copy of test results must be submitted to this Department (Water Resources Management Division) before the new watermain is placed into service.** In the event of any bacteria detected in the sample results, flushing and re-sampling may be attempted or the disinfection process will need to be repeated until results for two consecutive sets of samples are bacteria free. Where necessary, this Department should be contacted to determine provisions for the disposal of heavily chlorinated water.
15. For the purpose of disinfecting new or upgraded watermains, connection may only be made to the existing watermain provided a valve is installed that maintains a water tight seal. This valve may be operated to flush the new water extension before disinfection and post disinfection provided adequate measures and procedures are followed to avoid a backflow and contamination of the existing system.
16. The existing watermain that is being taken out of service must be permanently disconnected so as not to create a cross-connection with the town's water distribution system.

Development in WPWSA

17. All persons working on this project must be informed that they are within a Wellhead Protected Water Supply Area and must be made aware of all conditions of this Permit. A copy of this Permit must be on site during construction.
18. All equipment must be in good working order with no leaking fuel or oil. Refueling of heavy equipment is not allowed on site.
19. Any spills of gasoline, fuel or oil, regardless of volume, must be reported immediately to the Environmental Scientist at (709) 729-2539. Furthermore, all spills in excess of 70 litres shall be reported immediately to the 24 hour spill report line at (709) 772-2083 (call collect) or 1-800-563-9089.
20. All operations must be carried out in a manner that minimizes damage to land, vegetation and water courses, and which prevents pollution of water bodies. Please note that groundwater aquifers are considered water bodies.
21. The use of treated wood, including the use of treated utility poles, is limited to wood protected by copper azole preservative.
22. During construction and after the project is complete, the use and/or storage of fertilizers, pesticides, herbicides, petroleum solvents, chlorinated solvents, and preservatives is limited or restricted. Please contact the Environmental Scientist at (709)729-2539 for more information.
23. The parking, storage, and maintenance of heavy equipment is prohibited.
24. Equipment storage and maintenance facilities associated with this project must not be located within the Wellhead Protected Water Supply Area, and all maintenance other than emergency repairs must be performed outside the Wellhead Protected Water Supply Area.
25. Bulk fuel storage, including home heating fuel, is prohibited.
26. The use and/or storage of fertilizers, pesticides, herbicides, petroleum solvents, chlorinated solvents, and preservatives are prohibited.
27. Fuel/gasoline storage is limited to one 23 litre (5 Imperial gallon) approved container during both the construction and occupation period of the property. Furthermore, every precaution shall be made to prevent spills, leaks, or other discharges while filling from the container.
28. Liaison must be maintained with the appropriate Municipal Authority and Department official. If there are any specific problems (i.e., fuel spill or other potential water quality impairment), the Town Manager/Clerk and/or Mayor must be notified immediately, as well as the Environmental Scientist at (709)729-2539.
29. Officials of the Department and the appropriate Municipal Authority, Operator, or Wellhead Protection Committee may visit the site from time to time to ensure compliance with this Permit.
30. Any areas adversely affected by this project must be restored to a state that resembles the local natural conditions or must be grass covered. Further remedial measures to mitigate environmental impacts on water resources can and will be specified, if necessary in the opinion of the Department.

31. The Department reserves the right to require the proponent to cover all costs incurred by the proponent or this department that is associated with any water quality monitoring program that may be ordered by the Minister for the purpose of ensuring that the water quality is maintained within acceptable guidelines.
32. Any changes in the Town of Wabana Wellhead Protected Water Supply water quality resulting directly from this project, rendering the water unsuitable as a public water supply, are the responsibility of the proponent. The Minister may order the proponent to provide an alternate source of potable water to the affected community until water quality returns to an acceptable level.
33. A water quality monitoring program is not required at this time. However, the Department reserves the right to require that the proponent sample, analyze, and submit results of water quality tests, for the purpose of ensuring that the water quality of the surrounding aquifer(s), is maintained within acceptable guidelines. All analyses must be undertaken by a CALA accredited laboratory.
34. The permit holder, contractor, subcontractor or other persons associated with this project shall not cross, operate in, or disturb any body of water, either directly or by means of installing a bridge or culvert, without first obtaining a permit under Section 48 of the Water Resources Act SNL 2002 cW-4.01
35. Any significant changes in the permitted operations, developments or activities other than those specified in the application must be submitted in writing to the Department, and permitted in the form of an Amendment to this Permit, before they are undertaken.
36. Renewal of this permit shall require the submission of a written application, on the prescribed form, to the Department, and is subject to review by this Department and the appropriate Municipal Authority, Operator or Wellhead Protection Committee.
37. The permitted development activity is located at or near: 47.633631N, 52.949464W.
38. The well owner is responsible for compliance with this permit. This licence/permit does not constitute an acknowledgement of interest in any land claims adjacent.

General Alterations

39. Any work that must be performed below the high water mark must be carried out during a period of low water levels.
40. Any flowing or standing water must be diverted around work sites so that work is carried out in the dry.
41. Water pumped from excavations or work areas, or any runoff or effluent directed out of work sites, must have silt and turbidity removed by settling ponds, filtration, or other suitable treatment before discharging to a body of water. Effluent discharged into receiving waters must comply with the *Environmental Control Water and Sewage Regulations, 2003*.
42. All operations must be carried out in a manner that prevents damage to land, vegetation, and watercourses, and which prevents pollution of bodies of water.
43. The use of heavy equipment in streams or bodies of water is not permitted. The operation of heavy equipment must be confined to dry stable areas.
44. All vehicles and equipment must be clean and in good repair, free of mud and oil, or other harmful substances that could impair water quality.
45. During the construction of concrete components, formwork must be properly constructed to prevent any fresh concrete from entering a body of water. Dumping of concrete or washing of tools and equipment in any body of water is prohibited.
46. The bed, banks and floodplains of watercourses, or other vulnerable areas affected by this project, must be adequately protected from erosion by seeding, sodding or placing of rip-rap.
47. All waste materials resulting from this project must be disposed of at a site approved by the Department of Digital Government and Service NL.
48. Periodic maintenance such as painting, resurfacing, clearing of debris, or minor repairs, must be carried out without causing any physical disruption of any watercourse. Care must be taken to prevent spillage of pollutants into the water.
49. The owners of structures are responsible for any environmental damage resulting from dislodgement caused by wind, wave, ice action, or structural failure.

50. Sediment and erosion control measures must be installed before starting work. All control measures must be inspected regularly and any necessary repairs made if damage is discovered.
51. Fill material must be of good quality, free of fines or other substances including metals, organics, or chemicals that may be harmful to the receiving waters.
52. The attached Completion Report (Appendix C) for Permit No. 14023 must be completed and returned to this Department upon completion of the approved works. Pictures must be submitted along with the completion report, showing the project site prior to and after development.
53. This Permit is valid for two years from the date of issue. Work must be completed by that date or the application and approval procedure must be repeated.
54. The location of the work is highlighted on the Location Map for this Permit attached as Appendix D.
55. All work must be carried out within the Permit Holder's legal property boundaries.
56. This licence/permit does not constitute an acknowledgement of interest in any land claims adjacent.

Water Systems

57. Under no circumstances shall sewage be permitted to enter the waterline trench during or after construction.

Miscellaneous

58. The Permit Holder must prevent erosion of drainage ditches, streams or other natural bodies of water by installing rip-rap and/or sodding.

APPENDIX B
Special Terms and Conditions for Permit

1. The Permit Holder and its agent(s), subcontractor(s), and consultant(s) shall keep all systems and works in good condition and repair and in accordance with all laws, by-laws, directions, rules and regulations of any governmental authority. The Permit Holder or its agent(s), subcontractor(s), or consultant(s) shall immediately notify the Minister if any problem arises which may threaten the structural stability of the systems and works, endanger public safety and/or the environment or adversely affect others and/or any body of water either in or outside the said Project areas. The Permit Holder and its agent(s), subcontractor(s), and consultant(s) shall be responsible for all damages suffered by the Minister and Government resulting from any defect in the systems and works, operational deficiencies/inadequacies, or structural failure.
2. The Permit Holder and its agent(s), subcontractor(s), and consultant(s) shall operate the said Project and its systems and works in a manner which does not cause any water related and/or environmental problems, including but not limited to problems of erosion, deposition, flooding, and deterioration of water quality and groundwater depletion, in or outside the said Project areas. The Permit Holder and its agent(s), subcontractor(s), and consultant(s) shall be responsible for any and all damages associated with these problems caused as a result of changes, deficiencies, and inadequacies in the operational procedures by the Permit Holder or its agent(s), subcontractor(s), or consultant(s).
3. If the Permit Holder or its agent(s), subcontractor(s), or consultant(s) fails to perform, fulfil, or observe any of the terms and conditions, or provisions of this Permit, as determined by this Department, the Minister may, without notice, amend, modify, suspend or cancel this Permit in accordance with the *Water Resources Act*.
4. The Permit Holder and its agent(s), subcontractor(s), and consultant(s) indemnify and hold the Minister and Government harmless against any and all liabilities, losses, claims, demands, damages or expenses including legal expenses of any nature whatsoever whether arising in tort, contract, statute, trust or otherwise resulting directly or indirectly from granting this Permit, systems and works in or outside the said Project areas, or any act or omission of the Permit Holder or its agent(s), subcontractor(s), or consultant(s) in or outside the said Project areas, or arising out of a breach or non-performance of any of the terms and conditions, or provisions of this Permit by the Permit Holder or its agent(s), subcontractor(s), or consultant(s).
5. This Permit is subject to all provisions of the *Water Resources Act* and any regulations in effect either at the date of this Permit or hereafter made pursuant thereto or any other relevant legislation enacted by the Province of Newfoundland and Labrador in the future.
6. This Permit shall be construed and interpreted in accordance with the laws of the Province of Newfoundland and Labrador.

- cc: Jonathan Butt, P.Eng.
Englobe Corp.
39 Sagona Ave.
Mount Pearl NL A1N 4P9
Jonathan.Butt@englobecorp.com
- cc: Ms. Paula Dawe, P.Eng.
Manager, Water Rights, Investigations and Modelling Section
Water Resources Management Division
Department of Environment and Climate Change
P.O. Box 8700
4th Floor, West Block, Confederation Building
St. John's, NL A1B 4J6
pauladawe@gov.nl.ca
- cc: Eastern Lands Office
Fisheries & Land Resources
P.O. Box 8700
Howley Building, Higgins Line
St. John's NL A1B 4J6
easternlandsoffice@gov.nl.ca
- cc: Ms. Deneen Spracklin, P.Eng.
Manager, Drinking Water and Wastewater Section
Water Resources Management Division
Department of Environment and Climate Change
P.O. Box 8700
4th Floor, West Block, Confederation Building
St. John's, NL A1B 4J6
dspracklin@gov.nl.ca
- cc: Mr. Inayat Rehman, P.Eng.
Regional Engineer
Department of Transportation and Infrastructure
P.O. Box 8700
St. John's, NL A1B 4J6
inayatrehman@gov.nl.ca
- cc: Mr. Terry Battcock
Manager of Operations (Environmental Health)
Digital Government and Service NL
149 Smallwood Drive, Mount Pearl
PO Box 8700
St. John's NL A1B 4J6
tbattcock@gov.nl.ca
- cc: Fish and Fish Habitat Protection Program
Aquatic Ecosystems Branch
Fisheries and Oceans Canada
P.O. Box 5667
St. John's, NL A1C 5X1
dfo.fppnl-ppptnel.mpo@dfo-mpo.gc.ca

Appendix C - Completion Report

Pursuant to the *Water Resources Act*, SNL 2002 cW-4.01, specifically Section(s) 37, 61, 48

Date: **DECEMBER 10, 2024**

File No: **844.199.001**

Permit No: **WS14023-2024**

Permit Holder: **Town of Wabana
P.O. Box 1229
Wabana, NL
A0A 4H0
jordonblackwood@townofwabana.net**

Attention: **Jordan Blackwood**

Re: **Wabana - West Dam Water Supply Phase 4 (Waterline)**

Permission was given for : **the installation of 270 m of 50 mm PE waterline and all related appurtenances to connect Davidson Well (WS-G-0879) to the Scotia Road Well building (WS-G-0879) as described in the drawings titled, "West Dam Water Supply Phase 4 (Waterline)" as received from Englobe on August 2, 2024; 17-GI-21-00087.**

I (the Permit Holder named above or agent authorized to represent the Permit Holder) do hereby certify that the project described above was completed in accordance with the plans and specifications submitted to the Department of Environment and Climate Change and that the work was carried out in strict compliance with the terms and conditions of the Permit issued for this project.

Date: _____ Signature: _____

This completion report must be completed and forwarded to the following address upon completion of the approved work.

Department of Environment and Climate Change
Water Resources Management Division
PO Box 8700
St. John's NL A1B 4J6

APPENDIX D
Location Map for Permit

Town of Wabana (Wetland) - Wabana West Dam Water Supply

