

PERMIT TO CONSTRUCT

Pursuant to the *Water Resources Act*, SNL 2002 cW-4.01, specifically Section(s) 37

Date: **NOVEMBER 19, 2025**

File No: **844.049.1**

Permit No: **WS14622-2025**


Permit Holder: **Local Service District of Swift Current**
PO Box 149
Swift Current NL A0E 2W0
scbrlocalservicedistrict@outlook.com

Attention: **Tonia Crocker, Chair**

Re: **Swift Current - Hollett's Point Well Water Quality Upgrades**

Permission is hereby given for : **the installation of 5 micron cartridge filter, anion exchange unit with brine tank, retention tank, greensand filter, calcite contactor and all related appurtenances as described in the drawings and specification titled, "Hollett's Point Well Water Quality Improvement" as received from CBCL on July 31, 2025; 17-GI-24-00094.**

- This Permit does not release the Permit Holder from the obligation to obtain appropriate approvals from other concerned municipal, provincial and federal agencies.
- The Permit Holder must obtain the approval of the Crown Lands Administration Division if the project is being carried out on Crown Land.
- This Permit is subject to the terms and conditions indicated in Appendices A and B (attached).
- It should be noted that prior to any significant changes in the design or installation of the proposed works, or in event of changes in ownership or management of the project, an amendment to this Permit must be obtained from the Department of Environment and Climate Change under Section 49 of the *Water Resources Act*.



(for) MINISTER

APPENDIX A
Terms and Conditions for Permit

Water & Sewer General

1. Water pumped from excavations or work areas, or any runoff or effluent directed out of work sites, must have silt and turbidity removed by settling ponds, filtration, or other suitable treatment before discharging to a body of water. Effluent discharged into receiving waters must comply with the *Environmental Control Water and Sewage Regulations, 2003*.
2. All operations must be carried out in a manner that prevents damage to land, vegetation, and watercourses, and which prevents pollution of bodies of water.
3. Any areas adversely affected by this project must be restored to a state that resembles local natural conditions. Further remedial measures to mitigate environmental impacts on water resources can and will be specified, if considered necessary in the opinion of this Department.
4. All waste materials resulting from this project must be disposed of at a site approved by the Department of Digital Government and Service NL.
5. The works proposed must satisfy the requirements of the latest applicable codes and standards, and be consistent with or otherwise address the design criteria set out in this Department's publication *Guidelines for the Design, Construction, and Operation of Water and Sewerage Systems, 2005*, and as amended from time to time.
6. The work must be undertaken in strict compliance with the submitted documents and the latest version of the *Municipal Water, Sewer and Roads Master Construction Specifications*. A copy of all documents, including the *Municipal Water, Sewer and Roads Master Construction Specifications* must be available for viewing at the construction site office at all times.
7. Liaison is to be maintained with the Environmental Scientist representing the Drinking Water and Wastewater Section of this Department, during the construction and operation of the project. They shall be notified of the pre-construction and post-construction meetings so that they may attend, if deemed necessary. They can be reached at telephone (709) 729-2558.
8. Officials of this Department may visit the project from time to time to ensure that work is carried out within the provisions of this Permit, and is not creating any environmental hazard.
9. Any changes in the approved works, or works other than those specified in the application, must be submitted, in writing, to this Department, and approved, in the form of an Amendment to this Permit, prior to any work.
10. Copies of this Permit, as well as any subsequent Amendments, must be provided to the contractor(s) who will be carrying out these works, and to the engineer's site representative.
11. The attached Completion Report (Appendix C) for Permit No. 14622 must be completed and returned to this Department upon completion of the approved works. Pictures must be submitted along with the completion report, showing the project site prior to and after development.
12. This Permit is valid for two years from the date of issue. Work must be completed by that date or the application and approval procedure must be repeated.

13. The drinking water and wastewater system shall be operated and maintained in accordance with the Permit to Operate issued by this Department.
14. Management of stormwater is the responsibility of the municipality or LSD. Stormwater management should focus on ensuring that the post-development stormwater runoff rate will be equal to or less than the pre-development runoff rate. Any stormwater runoff has the potential to contribute to flooding downstream which may have liability issues for the municipality or LSD if not managed properly.
15. The Owner must update any drawings maintained of the drinking water or wastewater system to reflect the modification or replacement of the works, where applicable.

Miscellaneous

16. The Permit Holder must prevent erosion of drainage ditches, streams or other natural bodies of water by installing rip-rap and/or sodding.
17. The selected contractor must provide the town with a hard copy and a digital copy of the Operation and Maintenance Manual. A digital copy must be submitted to the Water Resources Management Division. The manual must include data for all major components of the plant/facility. The data must be for the particular units supplied and not a general description of units manufactured by the supplier.

Water Treatment

18. There shall be adequate storage handling facilities for 30 days of dry chemical supply.
19. All drains and vents shall be equipped with screens to prevent the entry of insects, birds and rodents.
20. The ends of drains and overflows shall be located so as to prevent erosion. Where necessary, concrete or similar splash plates shall be located below the end of the overflow, and the immediate surrounding area shall be filled to a depth of 10 cm with 19 mm minus stone to prevent ponding.
21. A backflow prevention device, in this case a hose connection vacuum breaker, non removable, meeting or exceeding CSA 64.2, shall be attached to any hose bibb connection, to prevent the possibility of contaminants entering the potable water distribution system due to back-siphonage.
22. All components, lubricants and chemicals provided shall be compatible for use with drinking water and shall meet the requirements of ANSI/NSF 60 Drinking Water Treatment Chemical Standard and ANSI/NSF 61 Drinking Water and System Component Standard and any other standard applicable to potable water.
23. Storage tank and pressure tank drain lines and overflows shall not be directly connected to the building floor drain, but shall be separated from the floor drain by an appropriately sized air gap. Drain lines from the storage tank and pressure tanks shall be protected from back-siphonage or back-pressure by an appropriate backflow prevention device.
24. A sample tap shall be provided so that water samples can be obtained from the raw water source and from an appropriate location after chlorination. Taps used shall be of the smooth-nosed type without interior or exterior threads and shall not have a screen, aerator or other such appurtenance.
25. The owner shall ensure that all chemicals used in the treatment process and all materials contacting the water are of Food Grade quality and meet both the American Water Works Association (AWWA) quality criteria as set out in AWWA standards and the American National Standards Institute (ANSI) and the National Sanitation Foundation (NSF) safety criteria as set out in ANSI/NSF 60 or ANSI/NSF 61 standards and any other applicable standards.

26. The water treatment plant including all interior and exterior water piping systems, all storage tanks including the finished water clear wells, filter media and other receptacles and appurtenances must be disinfected by approved methods such as described in the American Water Works Association Standards, Disinfection of Watermains, C651-99, Disinfection of Water Storage Facilities, C652-92 and Disinfection of Water Treatment Plants C653-87. It should be noted that the filter chambers must be disinfected prior to the placement of filter media and subsequently, the media disinfected as per the above quoted Standards. After final flushing, samples shall be collected and tested for bacteriological quality. The sampling locations shall be determined by the engineer. A copy of the test results shall be submitted to this Department (Water Resources Management Division) before the treatment plant is placed in service.
27. Residuals discharged from the water treatment plant must meet the requirements of the *Environmental Control Water and Sewage Regulations, 2003*. If monitoring shows non-compliance, the owner shall take corrective action and plan upgrades as necessary to achieve compliance.
28. Appropriate backflow prevention devices meeting or exceeding the CSA 64 Standard shall be installed on all potable water lines where a cross connection may exist or be created, to prevent the possibility of contaminants entering the potable water distribution system due to back-siphonage or back-pressure.

APPENDIX B
Special Terms and Conditions for Permit

1. The Permit Holder and its agent(s), subcontractor(s), and consultant(s) shall keep all systems and works in good condition and repair and in accordance with all laws, by-laws, directions, rules and regulations of any governmental authority. The Permit Holder or its agent(s), subcontractor(s), or consultant(s) shall immediately notify the Minister if any problem arises which may threaten the structural stability of the systems and works, endanger public safety and/or the environment or adversely affect others and/or any body of water either in or outside the said Project areas. The Permit Holder and its agent(s), subcontractor(s), and consultant(s) shall be responsible for all damages suffered by the Minister and Government resulting from any defect in the systems and works, operational deficiencies/inadequacies, or structural failure.
2. The Permit Holder and its agent(s), subcontractor(s), and consultant(s) shall operate the said Project and its systems and works in a manner which does not cause any water related and/or environmental problems, including but not limited to problems of erosion, deposition, flooding, and deterioration of water quality and groundwater depletion, in or outside the said Project areas. The Permit Holder and its agent(s), subcontractor(s), and consultant(s) shall be responsible for any and all damages associated with these problems caused as a result of changes, deficiencies, and inadequacies in the operational procedures by the Permit Holder or its agent(s), subcontractor(s), or consultant(s).
3. If the Permit Holder or its agent(s), subcontractor(s), or consultant(s) fails to perform, fulfil, or observe any of the terms and conditions, or provisions of this Permit, as determined by this Department, the Minister may, without notice, amend, modify, suspend or cancel this Permit in accordance with the *Water Resources Act*.
4. The Permit Holder and its agent(s), subcontractor(s), and consultant(s) indemnify and hold the Minister and Government harmless against any and all liabilities, losses, claims, demands, damages or expenses including legal expenses of any nature whatsoever whether arising in tort, contract, statute, trust or otherwise resulting directly or indirectly from granting this Permit, systems and works in or outside the said Project areas, or any act or omission of the Permit Holder or its agent(s), subcontractor(s), or consultant(s) in or outside the said Project areas, or arising out of a breach or non-performance of any of the terms and conditions, or provisions of this Permit by the Permit Holder or its agent(s), subcontractor(s), or consultant(s).
5. This Permit is subject to all provisions of the *Water Resources Act* and any regulations in effect either at the date of this Permit or hereafter made pursuant thereto or any other relevant legislation enacted by the Province of Newfoundland and Labrador in the future.
6. This Permit shall be construed and interpreted in accordance with the laws of the Province of Newfoundland and Labrador.

- cc: Ben Bickerton, P.Eng.
CBCL Limited - Halifax
P.O. Box 606
Halifax, NS, B3J 2R7
bbickerton@cbcl.ca
- cc: Ms. Deneen Spracklin, P.Eng.
Manager, Drinking Water and Wastewater Section
Water Resources Management Division
Department of Environment and Climate Change
P.O. Box 8700
4th Floor, West Block, Confederation Building
St. John's, NL A1B 4J6
dspracklin@gov.nl.ca
- cc: Richard Harvey, Ph.D., P.Eng.
Program - Lead - Drinking Water, Drinking Water & Wastewater Section
Water Resources Management Division
Department of Environment and Climate Change
RHarvey@gov.nl.ca
- cc: Mr. Inayat Rehman, P.Eng.
Regional Engineer
Department of Transportation and Infrastructure
P.O. Box 8700
St. John's, NL A1B 4J6
inayatrehman@gov.nl.ca
- cc: Mr. Michael Duke (Clarenville - Eastern)
Manager
Digital Government and Service NL
8 Myers Ave
Clarenville, NL A5A 1T5
michaelduke@gov.nl.ca

Appendix C - Completion Report

Pursuant to the *Water Resources Act*, SNL 2002 cW-4.01, specifically Section(s) 37

Date: **NOVEMBER 19, 2025**

File No: **844.049.1**
Permit No: **WS14622-2025**

Permit Holder: **Local Service District of Swift Current**
PO Box 149
Swift Current NL A0E 2W0
scbrlocalservicedistrict@outlook.com

Attention: **Tonia Crocker, Chair**

Re: **Swift Current - Hollett's Point Well Water Quality Upgrades**

Permission was given for : **the installation of 5 micron cartridge filter, anion exchange unit with brine tank, retention tank, greensand filter, calcite contactor and all related appurtenances as described in the drawings and specification titled, "Hollett's Point Well Water Quality Improvement" as received from CBCL on July 31, 2025; 17-GI-24-00094.**

I (the Permit Holder named above or agent authorized to represent the Permit Holder) do hereby certify that the project described above was completed in accordance with the plans and specifications submitted to the Department of Environment and Climate Change and that the work was carried out in strict compliance with the terms and conditions of the Permit issued for this project.

Date: _____ Signature: _____

This completion report must be completed and forwarded to the following address upon completion of the approved work.

Department of Environment and Climate Change
Water Resources Management Division
PO Box 8700
St. John's NL A1B 4J6