

This specification outlines the requirements for the installation of a project sign in location on or near the site of the work.

PART 1 REFERENCES

1.1 NOT APPLICABLE

PART 2 GENERAL

2.1 TIMING

- .1 The location of the sign is to be determined by the Owner and is to be installed in the first week that the Contractor's personnel mobilizes to site prior to any other work being performed.
- .2 A photo is to be submitted to the Owner immediately.
- .3 Sign to remain in place until 30 days after construction is complete and the project is ready for intended use.

PART 3 PRODUCTS

3.1 MATERIALS

- .1 Timber posts shall be Eastern Spruce or Fir.
- .2 All nails shall be galvanized.
- .3 Project sign is to be supplied by the Contractor. Project sign to be 1.22 m x 2.44 m and made of Dibond or 13 mm plywood or as otherwise approved by the Regional Engineer.

PART 4 EXECUTION

4.1 INSTALLATION

- .1 Refer to Drawing Index for standard drawing for the size of sign and lettering.
- .2 Refer to Drawing Index for standard drawings for the size and type of sign supports required.
- .3 Fasten panels to 100 mm by 100 mm posts as indicated, using 180 mm by 10 mm galvanized carriage bolts.
- .4 Each 100 mm by 100 mm post shall be in one length, set vertically in the ground a minimum of 900 mm.

- .5 Each 50 mm by 100 mm brace will be fastened to the post with a 180 mm by 10 mm galvanized carriage bolt.
- .6 After installation, backfill to the existing ground elevation and compact thoroughly.
- .7 Remove any debris from the Work Area.
- .8 Top of the sign to be 2.4 m above the ground.
- .9 Remove sign and make good the area 30 days after Total Performance.

## PART 5 PAYMENT

### 5.1 MEASUREMENT FOR PAYMENT

- .1 Measurement for payment will be by means of the number of each type of sign installed as noted in the Contract Documents.

### 5.15.2 BASIS OF PAYMENT

- .1 All costs associated with the work outlined in this specification shall be deemed to be included in the appropriate unit and lump sum prices quoted in the MERX Schedule of Quantities and Prices. The Owner will not approve any progress claims until the Project Sign and sign supports have been erected. Maintenance of the signs shall be considered part of the lump sum amount.