



**SECTION 201**  
**CLEARING AND GRUBBING**

**INDEX**

**201.01 DESCRIPTION**

**201.02 PERMITS AND AUTHORIZATION**

**201.03 CLEARING AND GRUBBING OPERATIONS**

**201.04 MEASUREMENT FOR PAYMENT**

**201.05 BASIS OF PAYMENT**

**201.01 DESCRIPTION**

Clearing and grubbing shall consist of the removal and disposal of all trees, brush, logs, surface boulders, stumps, roots, matted roots and other vegetation from within areas selected by the Engineer.

**201.02 PERMITS AND AUTHORIZATION**

The Contractor is required to obtain a permit to cut trees. Application for a permit should be made to the local office of the Department of Forest Resources and Agrifoods.

Should the Contractor wish to burn brush, then prior permission must first be obtained from the Department of Forest Resources and Agrifoods.

**201.03 CLEARING AND GRUBBING OPERATIONS**

Areas in which clearing and grubbing are to be carried out will be staked on the ground beforehand by the Engineer.

Where clearing and grubbing operations are required near a watercourse or water body, the Contractor shall ensure that a minimum 15 m "no grub" zone is left between the watercourse or water body and adjacent work area. This "no grub" buffer shall be clearly marked in the field by the Engineer prior to any grubbing so that the area is visible to heavy equipment operators.

The cutting of trees shall not commence until the Contractor has obtained a cutting permit.

The Department, should it so wish, may permit the Contractor to dispose of any timber cut on Crown Land to his advantage providing the requirements of the Crown Lands Act, with respect to royalties, etc., are met.

Where timber to be cleared and grubbed is on land belonging or leased to private individuals, crown corporations or companies, the timber does not become the property of the Contractor. The Contractor must make prior arrangements with land owners or lessee for the disposal of the timber.

The Contractor shall not proceed with any burning operations during the fire season without securing the permission of the Department of Forest Resources and Agrifoods. The Contractor shall take all necessary precautions to guard against damage to surrounding timber and shall assume all liability for claims which may arise from any such damage.

Surface boulders, regardless of their size, shall be considered as part of clearing and grubbing. All surface boulders shall be removed and disposed of along with the other clearing and grubbing debris.

## **FORM 201**

Clearing and grubbing debris shall be disposed of in a manner approved by the Engineer. The Contractor shall haul away and dispose of the clearing and grubbing debris in an approved waste disposal area. The approved waste disposal area shall be provided by the Contractor at his own expense. Clearing and grubbing debris shall be trimmed to sightly proportions.

Where clearing and grubbing takes place in preparation for a borrow area outside of the right of way then clearing and grubbing debris may be pushed upon adjacent land provided that in so doing the debris is not pushed onto land belonging to others, or pushed in or around stands of mature trees.

Where a significant quantity of topsoil exists and as directed by the Engineer, the Contractor shall stockpile topsoil separately from other material for possible rehabilitation work.

### **201.04 MEASUREMENT FOR PAYMENT**

Measurements will be made of the horizontal area actually cleared and grubbed from within the area staked out by the Engineer. These measurements shall be computed to obtain the area in hectares, measured to three decimal places.

Clearing and grubbing beyond the limits staked will not be measured for payment.

### **201.05 BASIS OF PAYMENT**

Payment at the contract price for Clearing and Grubbing shall be compensation in full for all labour, materials and equipment-use to carry out the work indicated in this specification or in any way connected with these operations.

No payment, other than that provided for in the contract price for Clearing and Grubbing, will be made for topsoil and surface boulders removed by clearing and grubbing operations, or for any and all haulage involved in clearing and grubbing debris disposal.