

## **SECTION 845**

### **EQUIPMENT OPERATION AND PREVENTION OF EROSION AND SILTATION**

#### **INDEX**

- 845.01 STORM WATER MANAGEMENT**
- 845.02 TEMPORARY TRAVEL ROUTES**
- 845.03 EROSION & SILT CONTROL MEASURES**
  - 845.03.01 GENERAL PROTECTION MEASURES**
- 845.04 LIMITATION OF OPERATION**

#### **845.01 STORM WATER MANAGEMENT**

The Contractor is responsible for storm water and drainage management during the period of the contract. This includes the collection, channeling, containment, settling, discharge and any other operation to effectively control storm runoff and prevent problems of erosion or siltation of adjacent or downstream areas. (See Section 815.07 Control and Treatment of Silted Water).

#### **845.02 TEMPORARY TRAVEL ROUTES**

Linear travel along the right of way by vehicles and equipment shall be restricted to one track or travel route, particularly during the early stages of opening access along the route, unless otherwise accepted by the Owner's representative. The route shall be maintained by the Contractor free of standing water. Surface drainage will not be permitted to run along the route which can generate extensive mud and silt, and adversely affect materials to be excavated such as grubbing, unsuitable material, and overburden. Surface drainage shall be vented off the route at frequent intervals. Where drainage courses are encountered, and frequent crossings are required, temporary pipes (CSP or iron) shall be installed to permit passage of equipment and vehicles in the dry, without causing erosion and siltation. At certain locations fording may be permitted by the Owners representative. (See Section 815.03 Fording of Watercourses).

#### **845.03 EROSION & SILT CONTROL MEASURES**

##### **845.03.01 GENERAL PROTECTION MEASURES**

The Contractor shall minimize terrain disturbance and erosion resulting from its activities. The Contractor shall, as part of its work, implement erosion and silt control measures where its activities result in a blockage of natural drainage, the diversion of natural drainage, or the exposure of soil or subsoil to potential erosion. Particular measures which may be required include:

- a) using an erosion control blanket;
- b) using an appropriate hydraulic mulch;
- c) spreading hay over exposed soils;
- d) spreading a thin layer of brush or slash over disturbed areas;
- e) the installation of baffles or sediment traps at appropriate intervals within the area of disturbance;
- f) the installation of drainage collectors across the disturbed area to channel drainage into vegetated areas;
- g) the re-routing of disturbed drainage courses back into the natural course;
- h) the stabilization of exposed soils at drainage locations with appropriate rip-rap;
- i) where so directed by the Owner's representative, to construct check dams to confine mud or slurry at such locations as unsodded ditch lines, catch-basins and culvert inlets;
- j) the pumping of silted water to settling or designated vegetated areas;
- k) the installation of sedimentation basins of adequate size at run-off locations from exposed areas to contain heavy silt and mud as directed by the Owner's representative.

#### **845.04      LIMITATION OF OPERATION**

During periods of heavy rain, where in the opinion of the Owner's representative, the movement of excavated material and equipment may give rise to extensive mud conditions, or the potential to seriously impact watercourses, or adjacent land, the Contractor may be required to suspend operations until such time as site conditions allow operations to resume. The Contractor shall not be paid for such downtime.