

SECTION 911
ICE BREAKERS

INDEX

911.01 SCOPE

911.02 MATERIALS

911.03 ERECTION

911.04 UNASSIGNED

911.05 MEASUREMENT FOR PAYMENT

911.06 BASIS OF PAYMENT

911.01 SCOPE

The scope of this specification is to cover the supply and erection of steel ice breakers on concrete piers.

911.02 MATERIALS

The ice breaker shall be fabricated in structural steel to G40-21M (300W). Fabrication shall be in accordance with the detailed drawings.

After fabrication the ice breaker shall be hot dip galvanized in accordance with CAN/CSA-G164.

911.03 ERECTION

The ice breaker shall be placed in the form work prior to concrete placement. Elevations shall be approved by the Engineer.

Any damage done to the galvanizing prior to installation shall be repaired in an acceptable manner and provide a galvanized coating comparable to that provided by CAN/CSA-G164.

911.04 UNASSIGNED

911.05 MEASUREMENT FOR PAYMENT

Each ice breaker on each pier will be considered a unit.

911.06 BASIS OF PAYMENT

Payment for each unit will be as per the tendered item "Supply and Install Steel Ice Breaker".