

SECTION 207

BORROW

INDEX

207.01 SCOPE

207.02 PERMITS

207.03 DESCRIPTION

207.03.01 Delays and Provision of Borrow Sites

207.03.02 Siting of Borrow Sites

207.03.03 Operation of Borrow Sites

207.03.04 Abandonment and Rehabilitation

207.04 MATERIAL CLASSIFICATION

207.05 MEASUREMENT FOR PAYMENT

207.06 BASIS OF PAYMENT

207.01 SCOPE

This specification concerns borrow where the Department supplies the material source.

However, where the Contractor is required to supply the source of material, as in contract items such as, "Supply Rock Fill in Place" or "Supply Other Material Fill in Place", then the requirements are covered separately in Section 310.

207.02 PERMITS

Approval by the Department of Industry, Energy and Technology is required for the establishment of borrow sites outside of the highway right of way by way of a quarry permit or quarry lease.

207.03 DESCRIPTION

When sufficient quantities of material suitable for highway fills are not obtainable from the various excavations required for the construction of the highway, then the Owner's Representative will authorize the provision of borrow material to be obtained from borrow sites as the Owner's Representative requires.

This work shall include all materials and labour required to excavate borrow materials, hauling up to 1 kilometre, handling and incorporation of the materials into fill construction in accordance with Section 204.

207.03.01 Delays and Provision of Borrow Sites

Where borrow sites are located outside the limits of the right of way, they will be provided and paid for by the Department.

Before the Department directs the Contractor to obtain borrow from a particular area, the Department will make effort to determine the suitability of the material. However, if after borrow operations have begun, the Department determines the material is no longer suitable, the borrow area may no longer be used to obtain material.

In the event the Contractor is delayed while another borrow site is being obtained, the Department will not assume responsibility for the first 30 days of such a delay and the Contractor shall indemnify and save harmless the Minister from all suits and actions for damages resulting from the first 30 days of the delay. The Department will consider extending the Contract Time for such reasonable time as the Owner may decide in consultation with the Contractor.

207.03.02 Siting of Borrow Sites

Borrow pits and quarries shall be located and confined to such limits as the Owner's Representative may direct.

Where borrow sites are necessary outside the highway right of way, the borrow site shall be subject to all terms and conditions of the quarry permit or lease issued by the Department of Industry, Energy and Technology. A buffer strip of 200 metres shall be maintained between the highway right of way and the borrow site. Any trees within the buffer strip shall not be disturbed or damaged.

Upon completion of the borrow operation, the borrow site shall not be subject to ponding of water. The Contractor shall ensure that the borrow site is free draining.

All access roads to the borrow site shall be bridged or culverted where watercourses are crossed.

207.03.03 Operation of Borrow Sites

The Contractor shall clear and grub the borrow site before excavation begins, without causing disturbance or damage to the surrounding trees.

The Contractor shall be responsible for all damages to utility lines and adjoining property caused by blasting or from any cause whatsoever resulting from any of their operations in connection with the work.

All available topsoil or organic matter which overlies the borrow site shall be stockpiled without causing disturbance or damage to the surrounding trees.

Trees cut within the borrow area and not required for Departmental use will become the property of the Contractor.

Any unwatering necessary in the borrow area shall conform to the requirement of Section 180.

207.03.04 Abandonment and Rehabilitation

Before closure, the borrow site shall be trimmed and left neat and regular with side slopes conforming to the requirements set forth in the quarry permit or quarry lease issued by the Department of Industry, Energy and Technology or as directed by the Owner's Representative.

In all borrow operations, excavation faces shall be rehabilitated in accordance with the terms and conditions of the quarry permit or quarry lease, or sloped to the satisfaction of the Owner's Representative, as applicable.

Any available topsoil or organic material stockpiled previously shall be spread over the slopes to assist in revegetation. Where possible, borrow sites shall be hand seeded with a clover and hayseed mixture.

Waste material shall be disposed of in accordance with Division 8.

After completion of the operation or during periods of winter shutdown, the access road shall be ditched or barriers erected to prevent vehicular access unless instructed otherwise by the Owner's Representative. Earth barriers shall be graded and trimmed to sightly proportions.

207.04 MATERIAL CLASSIFICATION

Borrow materials will be classified as either "Solid Rock", "Rock Borrow", "Other Material", or "Other Material Borrow" in accordance with Section 205.

207.05 MEASUREMENT FOR PAYMENT

Measurement for payment will only include measurement of quantities that are required by the Owner's Representative to complete the Work.

Large rock fragments too large to be incorporated into the fill shall be measured and their volumes subtracted from the final cross section volumes. Calculations for volume of large rock fragments shall be the product of the three maximum rectilinear dimensions of the fragments.

Payment by Volume

For borrow materials described in Section 207.04, that are to be paid for by the volume of borrow material, then such materials shall be measured in cubic metres rounded to the nearest whole number.

The quantity to be measured shall be the number of cubic metres of excavated material as shown on the cross section sheets between the original position of the ground lines as cross sectioned after grubbing operations have been completed, and the completed and accepted excavation lines. The volume of this excavation will be computed by the average end area method of computation or as wedges or pyramids, as the case may be, when terminating at grade points.

Payment by Weight

For borrow materials, described in Section 207.04, that are to be paid for in terms of the number of tonnes, then such materials shall be weighed on scales. The weighing of materials shall be in accordance with the requirements of Section 501. Only loads certified by the Department personnel as being placed in the works shall be included in the measurement for payment. The weight shall be computed in tonnes, rounded to one decimal place.

207.06 BASIS OF PAYMENT

Where the contract includes quantities for "Rock Borrow", then all required excavation of solid rock from borrow areas will be paid for at the contract price for "Rock Borrow".

However, should the contract not include quantities for rock borrow, then all required excavation of solid rock from borrow sites will be paid for at the contract price for "Excavation Hauled 1 kilometre or Under, Solid Rock".

Where the contract includes quantities for "Other Material Borrow", then all required excavation of other material from borrow areas will be paid for at the contract price for "Other Material Borrow".

However, should the contract not include quantities for other material borrow, then all required excavation of other material from borrow areas will be paid for at the contract price for "Excavation Hauled 1 kilometre or Under, Other Material".

Payment shall be at the contract unit price per cubic metre, or per tonne, for either "Solid Rock", "Rock Borrow", "Other Material" or "Other Material Borrow", as the case may be, hauled 1 kilometre or under. Such payment shall be full compensation for all work herein described together with all materials, labour, and equipment use required to carry out excavating, handling, provision for weighing (if appropriate), hauling up to 1 kilometre and placing and compacting in a fill as described in Section 204.

However, clearing and grubbing shall be paid for separately in accordance with Section 201. Should the contract not include quantities for "Clearing and Grubbing", then all clearing and grubbing work will be paid for at the contract price for "Clearing" and "Grubbing", as appropriate.

Where the Owner's Representative requires that borrow material be hauled in excess of 1 kilometre, payment for overhaul will be made in accordance with Section 215.